



CONTRACT NO. LB-2045-000-002
**Install Electrical Isolation Points
on Eastbound Bay Bridge**
SPECIAL PROVISIONS

SP 1-1 PROJECT DESCRIPTION

CONTRACT NO.: **LB-2045-000-002**

TITLE: **Install Electrical Isolation Points on Eastbound Bay Bridge**

FACILITY: William Preston Lane Jr. Memorial Bridge ("LMB")

LOCATION: Anne Arundel and Queen Anne's Counties

ADVERTISED: **June 29, 2011**

PRE-BID MEETING: **July 15, 2011 at 10:00 a.m.** in the Conference Room at the Maryland Transportation Authority, Administration Building, 303 Authority Drive, 2nd Floor, Baltimore, MD 21222 (Please use side entrance closest to Key Bridge)

PROJECT CONTACT: Project Manager: Mr. David Dabkowski (410) 537-7852
Procurement Officer: Mr. Harry Johnson (410) 537-7522

BIDS DUE: **12 Noon, August 03, 2011** in the Bid Box at the Maryland Transportation Authority, Administration Building, 303 Authority Drive, 2nd Floor, Baltimore, MD 21222 (Please use side entrance closest to Key Bridge)

CLASSIFICATION: Class – C (\$500,001–\$1,000,000)

CONTRACT TIME: Three Hundred Fifteen (315) Calendar Days

LIQUIDATED DAMAGES: **\$1,000.00 per Calendar Day**

MINIMUM MBE GOALS: Overall 28%
No subgoals

BID DOCUMENTS: Bid documents can be downloaded from <http://www.emarylandmarketplace.com>. Any questions regarding how to get to this website, please contact the Division of Procurement and Statutory Program Compliance at (410) 537-7800.



SP 1-1 DESCRIPTION

This project shall furnish and install 4 electrical isolation points on the south bridge of the William Preston Lane Jr. Memorial Bridges ("LMB") and necessary access ladders to support fast access to the isolation points. Proposed isolation points will provide ability to segment and isolate portions of the 5KV feeder so that faults are easier to find and non-faulted portions of the electrical system can be more quickly isolated from the faults and restored to operation.

SP 1-2 SPECIFICATIONS

All work on this project shall conform to the Maryland Department of Transportation, State Highway Administration's Specifications entitled, "Standard Specifications for Construction and Materials" dated July 2008, revisions thereof, or additions thereto, and the Special Provisions included in this Invitation for Bids.

SP 1-3 ORIGINAL FACILITY PLANS AND SITE VISITS

The original facility plans are on file at the Engineering/Finance Building of the Francis Scott Key Bridge and will be made available for inspection to prospective bidders. Parties interested in viewing the plans should contact David Dabkowski at (410) 537-7852. Parties interested in visiting the site should contact the following:

William Preston Lane, Jr. Memorial Bridge – Mr. Gordon Garrettson, Facility Administrator at (410) 537-6659.

SP 1-4 PROMPT PAYMENT TO SUBCONTRACTORS

The prime Contractor is responsible for making timely payments to all Subcontractors and Suppliers and provide written certification as required in Section 17-106 of the State Finance and Procurement Article of the Annotated Code of Maryland, as amended.

This contract requires the Contractor to make payment to all Subcontractors within ten (10) days of receiving payment from the Authority.

Each month, the construction Project Engineer will review the current pay items with the prime Contractor and all involved Subcontractors to ensure that all work satisfactorily completed within specifications is included in the monthly progress payment. For payment purposes, the same quantity totals used to compute the payment to the prime Contractor will be the basis for payment to the Subcontractor.