



**BRIDGE DECK OVERLAY & MISCELLANEOUS  
REPAIRS FOR I-895A NB RAMP OVER  
I-895B & QUARANTINE ROAD OVER MD-695**

**SPECIAL PROVISIONS**

Contract No. MA 2581-000-006

1 of 10

**SP 1-1 PROJECT DESCRIPTION**

CONTRACT NO.: MA 2581-000-006

PROJECT MANAGER: Mitchell Dobres

TITLE: Bridge Deck Overlay & Miscellaneous Repairs for I-895A NB Ramp over I-895B & Quarantine Road over MD-695

FACILITY: Baltimore Harbor Tunnel Thruway and Francis Scott Key Bridge

COUNTY: Anne Arundel County and Baltimore City

ADVERTISED: January 11, 2012

PRE-BID MEETING: 10:00 a.m. on January 31, 2012  
In the 2<sup>nd</sup> floor Conference Room at the Maryland Transportation Authority Francis Scott Key Bridge, 303 Authority Drive Baltimore, MD 21222.

PROJECT CONTACT: Project Manager: Mr. Mitchell Dobres at (410) 931-0808  
Procurement Officer: Mr. Harry Johnson at (410) 537-7522

BIDS DUE: **12 Noon, February 17, 2012**, Bid box on the second floor of the Administration building at the Maryland Transportation Authority, 303 Authority Drive Baltimore MD 21222

CLASSIFICATION: Class - D (\$1,000,001 to \$2,500,000)

CONTRACT TIME: 540 Calendar Days

LIQUIDATED DAMAGES: **\$1,010.00 per Calendar Day**

MINIMUM MBE GOALS: **Overall 28%**  
**(7% African American Owned, 4% Asian American Owned, 17% Other)**

BID DOCUMENTS: Bid documents can be downloaded from <http://www.emarylandmarketplace.com>. Any questions regarding how to get to this website, please contact the Division of Procurement and Statutory Program Compliance at 410-537-7832.



## BRIDGE DECK OVERLAY & MISCELLANEOUS REPAIRS FOR I-895A NB RAMP OVER I-895B & QUARANTINE ROAD OVER MD-695

**SPECIAL PROVISIONS**

Contract No. MA 2581-000-006

2 of 10

### PROJECT SCOPE

The work to be performed under this contract is located at Structure No. AAY04500 carrying the I-895A ramp over I-895B and Structure No. BCZ50100 carrying Quarantine Road over MD-695. Structure No. AAY04500 is located in Anne Arundel County and Structure No. BCZ50100 is located in Baltimore City.

The scope of work includes, but is not limited to the following items:

- 1) Structure No. AAY04500 – I -895A NB Ramp over I-895B
  - Remove 3 inches of the existing concrete deck and replace it with a Latex Modified Concrete Overlay.
  - Complete concrete substructure repairs.
  - Remove existing bearings at all piers and replace them with new steel bearings.
  - Rebuild top portion of the pier cap sized to accommodate new bearings at all piers.
  - Complete additional miscellaneous repairs as shown in the Contract Documents and as directed by the Engineer.
  - Provide necessary maintenance of traffic to complete the work as shown in the Contract Documents.
  
- 2) Structure No. BCZ50100 – Quarantine Road over MD-695
  - Remove 3 inches of the existing concrete deck and replace it with a Latex Modified Concrete Overlay.
  - Remove existing roadway joints in the deck and concrete barriers and replace them with new silicone seal and retainer angle roadway joints and installing drainage troughs beneath the joints.
  - Complete concrete substructure repairs.
  - Clean and paint all structural steel in the bridge superstructure.
  - Complete additional miscellaneous repairs as shown in the Contract Documents and as directed by the Engineer.
  - Provide necessary maintenance of traffic to complete the work as shown in the Contract Documents.